



PRIMEWAVE

FINANCIAL PROPOSAL

Almabani Section 2

Road & Tunnel Lighting Control System

Casambi Architecture Replacement

Document	Technical Proposal, Rev. 03
Project	Almabani Section 2
Prepared by	Primewave
Date	May 2026
Scope	Supply of hardware, drawings, configuration and system settings. Installation by others.

8. Financial Section

Full Bill of Quantities for the supply scope. Installation, civil works and electrical wiring are not included and are by the appointed installation contractor.

#	Category	Description	Unit	Qty	Unit Price (SAR)	Total (SAR)
A. Street lighting control: fully addressed LoRaWAN architecture						
1	Zhaga 18 Book LED Driver	Shelly-based Sx18s compatible LED driver, LoRaWAN Ready, 400W max	pcs	2,898	280	811,440
2	LoRaWAN gateways	Flashnet IOTNETPRO HUB. 8-channel SX1301, 868 MHz, 4G LTE, GPS, IP67	pcs	6	57,980	347,880
3	High-gain antennas	8 dBi LoRa outdoor antenna with surge arrester and 5m cable	set	6	3,800	22,800
4	Gateway enclosures	IP66 enclosure with thermostatic ventilation, 24VDC PSU, surge protection	pcs	6	2,700	16,200
5	IP66 Box Enclosures	IP66 Box enclosure (Plastic)	pcs	3,232	90	290,880
Subtotal, Section A						1,489,200
B. DALI Control and Servers						
1	Central servers	Industrial PC server, 19 inch rack mount, RAID-1, redundant PSU	pcs	5	18,000	90,000
2	DALI output modules	DALI PRO 2 IOT 20X1 lighting control panel module	pcs	58	4,200	243,600
3	Outdoor portal sensors	External light sensor, V-lambda compensated, DALI output, IP65, sun shade hood	pcs	9	2,850	25,650
	Lighting Scene Controller	Atios Gateway Controller, MQTT-enabled, DALI, KNX, Matter Support	pcs	5	4,855	24,275
	Power Supply	Farnell VDC DIN-RAIL power supply.	pcs	5	315	1,575
	Photometer	Outdoor IP65-rated wall-mounted photometer, Including all accessories and mounting brackets. Excluding Housing unit.	pcs	9	1,910	17,190
Subtotal, Section B						321,290
C. Engineering, configuration and commissioning support (Professional Services)						
1	Professional Services package	Detailed engineering and design, RF site survey, system configuration of all 2,898 poles, wall-mounted sensors and light sensors. Configuration of DALI devices and network.	lump	1	80,000	80,000
Subtotal, Section D						80,000

Financial Summary

Section	Description	Amount (SAR)
A	Street lighting control hardware	1,489,200
B	DALI Control and Servers	321,290
C	Professional Services (bundled)	80,000
Subtotal (excluding VAT)		1,890,490
VAT (15%)		283,573.50
TOTAL INCLUDING VAT		2,174,063.50

End of Proposal